

Northeast Utilities Service Company P.O. Box 270 Hartford, CT 06141-0270 (860) 665-5000 www.nu.com

July 22, 2009



CONNECTICUT SITING COUNCIL

Robert Carberry / +r

Mr. S. Derek Phelps Executive Director Connecticut Siting Council 10 Franklin Square New Britain, CT 06051

Re: Docket No. 370 - CT Greater Springfield Reliability Project

Dear Mr. Phelps:

This letter provides the response to requests for the information listed below.

Response to OCC-01 Interrogatories dated 04/02/2009 OCC-001-SP03

Very truly yours,

Robert Carberry Project Manager

NEEWS Siting and Permitting

NUSCO

As Agent for CL&P

cc: Service List

The Connecticut Light and Power Company Docket No. 370

Data Request OCC-01 Dated: 04/02/2009 Q-OCC-001-SP03 Page 1 of 4

Witness:

CL&P Panel

Request from:

Office of Consumer Counsel

Question:

Since filing its Application, has CL&P become aware of any statements in that Application that require correction or clarification? If so, please provide such corrections/clarifications. Please treat this interrogatory as a continuing request, which CL&P should update periodically as appropriate.

Response:

- On page Q-3 of the Application, CL&P omitted to include a Stream Channel Encroachment Line
 permit from the Connecticut Department of Environmental Protection. This permit regulates the
 placement of structures or vegetation clearing within state-designated stream-channel
 encroachment lines.
- 2. In the Direct Testimony of Robert Carberry and Scott Newland that was filed on July 7, 2009, the following changes are needed:
 - The revisions to magnetic field data in Table 7 on page 12 of Appendix O-1 (reference response OCC-01, Q-OCC-001-SP02) also apply to the table on page 39 of the testimony. A replacement page 39, included as page 2 of 4 of this response, incorporates and highlights these changes.
 - With the above change, the first magnetic field number in a question on the top of page 40 should be 2.4 mG, not 2.6 mG.
 - Two tables on page 42 of the testimony contain incorrect data. A replacement page 42, included as page 3 of 4 of this response, incorporates and highlights these corrections.
 - A table on page 53 drew data from the table on page 39, so also needs correction. A
 replacement page with this correction, and also a correction to a number in the question on
 this page (37 should be 3.7) is included as page 4 of 4 of this response. The corrections
 are highlighted.
 - Throughout the testimony, the acronym "FDMP" should be "FMDP".

- Q. Did CL&P evaluate other reduced-EMF designs for this focus area besides the delta design it is recommending?
- A. Yes, as set forth in detail in the FMDP, CL&P evaluated a total of seven alternative designs. The results of that evaluation are set forth in summary form in the following table:

Granby Jct. to CT / MA Border Comparison to Existing Conditions Line Configuration and Magnetic Fields @ ROW Edges

| X S2 Configuration | Typical Structu | re Height (ft.) | AAL Case | |
|---|-----------------------|-----------------|-------------------------|-------------------------|
| obosobkus okonopiis 🗗 kiri 1870 (List | Existing To Remain | New | W/N ROW Edge (mG) | E/S ROW Edge (mG) |
| Existing Lattice Towers Pre- project | 70 | | 8.7 | 0.1 |
| Base Line Design H-Frame | 70 | 90 | 23.5 | 12.6 |
| Alt 1 – H Frame + 20 feet | 70 | 110 | 22.8 | 12.3 |
| Alt 2 – Delta | 70 | 110 | 17.9 | 9.8 |
| Alt 3 – Delta + 20 ft. | 70 | 130 | 15.7 | 9.2 |
| Alt 4 – Vertical | 70 | 130 | 15.6 | 9.6 |
| Alt 5 – Vertical + 20 ft | 70 | 150 | 13.0 | 9.0 |
| Alt. 6 – Split Phase | 70 | 130 | 2.4 | 1.9 |
| Alt 7 345/115 Composite | N/A | 130 | 18.9 | 8.3 |

Q. What is "split phasing" of a line?

A. A transmission circuit is usually comprised of three conductors (or conductor bundles), one for each "phase." This configuration employs six, rather than three, phases, thus reducing the current in each of them one by one-half. The phases of the two sets of conductors are then arranged on the support structures so that the magnetic fields associated with each set of three phase conductors acts to partially cancel the fields from the other. This combination of reduced currents and mutual cancellation dramatically reduces MF levels at the ROW edges.

- Q. What are the magnetic field levels that would be associated with each of the reduced MF strategies considered in the supplemental FMDP?
- A. They are set forth in the following table, which also appears as FMDP Table 7:

FMDP Table 7: Magnetic Field Management Results for a 3.7-Mile Section of the GSRP – Massachusetts Southern Route Alternative ROW (Enfield) (AAL Case)

| XS-S07 Cross Section Configuration S | Total | Average Annual Load Case | | | | Cost | | |
|--------------------------------------|-------------------------------------|--------------------------|----------------|---------------|----------------|---------------|------------------------|-------------------------|
| | Typical Structure Height (ft) | | North ROW Edge | | South ROW Edge | | Cost | |
| | | | Level (mG) | Change (%) | Level (mG) | Change (%) | Section Amount (\$) | Project Increase (%) |
| Base Line Design H-Frame | 90 | 277.7 | 17.3 | STUMBBURS. | 15.2 | | \$11,714,000.00 | - |
| Alt 1 - H-Frame +20 feet | 110 | 134.9 | 10.3 | - 40% | 14.3 | - 6% | \$12,225,000.00 | 0.3% |
| Alt 2 - Delta Configuration | 110 | 170.5 | 12.1 | - 30% | 11.9 | - 22% | \$15,067,000.00 | 2.2% |
| Alt 3 - Delta +20 feet | 130 | 85 | 10 | - 42% | 10.9 | - 28% | \$16,908,000.00 | 3.4% |
| Alt 4 - Vertical Configuration | 130 | 143.8 | 22.3 | + 29% | 11.9 | - 22% | \$15,998,000.00 | 2.8% |
| Alt 5 - Vertical +20 feet | 150 | 67.1 | 24 | + 39% | 10.8 | - 29% | \$17,432,000.00 | 3.7% |
| Alt 6 - Split Phase | 130 | 81.5 | 15.4 | - 11% | 2.5 | - 84% | \$26,631,000.00 | 9.6% |
| Alt 7 - 345/115-kV Composite | 130 | 137.6 | 17.2 | - 1% | 9.4 | - 38% | \$27,527,000.00 | 10.2% |

- Q. How would the post-project fields and conditions compare to the preproject fields and conditions, if overhead line construction were used for the entire Connecticut portion of the Southern Route?
 - A. The following table provides such a comparison:

Comparison to Existing Conditions Structure Configuration and Magnetic Fields @ ROW Edges

| XS-S07 Configuration | Typical Structu | re Height (ft.) | AAL Case | |
|---------------------------|-----------------------|-----------------|-------------------------|-------------------------|
| | Existing To Remain | New | W/N ROW Edge (mG) | E/S ROW Edge (mG) |
| Existing H-Frame | 60 | | 7 | 0.3 |
| Base Line Design H-Frame | 60 | 90 | 17.3 | 15.2 |
| Alt 1 – H Frame + 20 feet | 60 | 110 | 10.3 | 14.3 |
| Alt 2 – Delta | 60 | 110 | 12.1 | 11.9 |
| Alt 3 – Delta + 20 ft. | 60 | 130 | 10 | 10.9 |
| Alt 4 – Vertical | 60 | 130 | 22.3 | 11.9 |
| Alt 5 – Vertical + 20 ft | 60 | 150 | 24 | 10.8 |
| Alt. 6 – Split Phase | 60 | 130 | 15.4 | 2.5 |
| Alt 7 345/115 Composite | N/A | 130 | 17.2 | 9.4 |

| BMP Focus Area | West/North ROW* | East/South ROW | |
|---|-------------------------|----------------|--|
| Pre-project | 8.7 | 0.1 | |
| Post-project BMP Delta Design | 17.9 | 9.8 | |
| Post Project Split-Phase | 2.4 | 1.9 | |
| Post- | project, UG variation (| in streets) | |
| Edge of ROW (existing lines, new loads) | 3.2 | 0.5 | |
| 25' from cables in streets 2.6 | | 5.6 | |

Therefore, if the primary objective in siting the line was to minimize magnetic field exposures, the choice would be a split-phase overhead line configuration, rather than an in-road underground line installation.

(ii) Connecticut Portion of Southern Route Alternative

- Q. Now let us turn briefly to the application of the presumption of section 16-50p(i) to the FMDP for the Connecticut Portion of the Southern Route

 Alternative. Has CL&P evaluated an underground variation that would avoid the 3.7-mile BMP focus area along this route that you described earlier?
- A. Yes, initially we looked at both in-row and street variations, but it is likely that only the latter could qualify for environmental permitting. This would be an XLPE cable system installed in streets for a distance of 4.3 miles. The planning grade comparative cost estimate is as follows: