

DOT DESIGN PROCESS INTEGRATED ENVIRONMENTAL REVIEW

How Environmental Permits/Commitments are administered by the Department


Environmental Summit

November 20, 2018

DOT Capital Program



- 87 106 Projects
 Administered per year
- 33% of projects that involve DEEP input.



Capital Plan Development

- Projects are Programmed/Initiated
 - Transportation Asset Management Plan
 - Public Transportation
 - Rail, Bus, Transit Districts
 - Highway & Bridge
 - Safety, System Preservation, Mobility Enhancements, Congestion Relief, and Criticality
 - Complete Streets safe traffic for pedestrians, bikes, etc.
 - Locally Administered Projects
- Projects are Funded
 - Federal Typically 80% Federal/20% State
 - State Only






Who is Responsible?



COMMISSIONER OF TRANSPORTATION JAMES P. REDEKER

| BUREAU OF ENGINEERING & CONSTRUCTION | BUREAU OF PUBLIC TRANSPORTATION | BUREAU OF POLICY & PLANNING | BUREAU OF FINANCE & ADMINISTRATION | BUREAU OF HIGHWAY OPERATIONS |
|---|---|-----------------------------|------------------------------------|---|
| Lead Design Units Environmental Permit Coordination Environmental Compliance Hydraulics & Drainage Construction | Lead Design Units Rail bridges Railroads Public Trans Facilities | Environmental Planning | • \$ • Safety | Maintenance Activities Drainage Roadways Bridge Electrical Landscape |



Bureau of Engineering & Construction




Bureau Chief Mark Rolfe, PE

Engineering Administrator

Scott Hill, PE


Construction Administrator


Ravi Chandran, PE



Construction

Construction
Administrator






Lead Design Units

OF TRANSO

Develop Construction Plans & Specifications for

State Administered Projects

- Project Management
- Design
- Utility Coordination
- Public Involvement
- Rights-of-Way Coordination



Complete Permit Plan Sets & Permit Applications

Environmental Planning (OEP)



Water and Natural Resources Unit

- Permit Application Development, Oversight & Review
- Coordination with Regulatory Agencies
- Wetland Delineations & Function and Values
- Listed Species and Fisheries Coordination
- Mitigation Development, Long term Monitoring and Stewardship

Water and Noise Compliance Unit

- Develop Environmental Specifications/Special Provisions
- Plan Reviews for Constructability
- Ensure Project Compliance during Construction
- Plantings and Invasive Species Removal Oversight during Construction

Environmental/Historic Documents Unit


- NEPA/CEPA level of Documentation Determinations, Coordination and Oversight
- Historic/Archaeological Investigations
- Section 106 Compliance, Mitigation Development and Coordination



Environmental Permit Coordination (EPC)



- Liaison between Engineering and OEP
 - Coordination, Education, Support, Facilitation
 - Assist Engineers with understanding environmental requirements
 - Assist Planners with understanding engineering requirements
 - Develop standards
 - Permit Plan Sets
 - Specifications
 - Details
 - Tracking of design process
- Facilitate process improvements



Hydraulics & Drainage



- Management of Flood Management Certification
 - FM General Department Projects
 - FM MOU Municipal Projects
- Hydraulics design/review on all projects
 - Major culverts and bridge crossings
 - Storm drainage systems
 - Temporary Bypass facilities
- Bridge safety/evaluation
 - Bridge scour/stream stabilities studies
 - Scour countermeasures and channel protection
- Design of fish & animal passage



Construction




- Design Phase Office of Construction
 - Constructability Review Water Handling
- Construction Phase District Construction
 - Oversight and Administration of projects
 - District Environmental Coordinators Tracking of commitments and permit adherence

Environmental Compliance (OEC)



- Management of contaminated soil, groundwater,
 & hazardous materials on Department projects
- Investigation and remediation of Department legacy sites
- Facility compliance (Industrial Stormwater, SPCC, etc.)
- MS4 Compliance

What is the Process?



PROJECT DESIGN TIMEFRAME

Construction
Begins
(Time of Year
Restrictions)

CONNECTICU

to OEP.

Are Review

Acceptable?

Comments

to OEP.

Are Review

Comments

Acceptable'

OEP.

Are Review

Comments


Acceptable?

*Disclaimer: Process maps are intended for guidance. Task duration estimates and procedure may vary based on project. Project managers may vary from mapped procedures on an as-needed

Microsoft Project



| | | 0 | | Duration | Start | Finish | Pre | 1st Quarter 3rd Quarter | | | | rter | |
|---|-----|---|---|------------|-------------|-------------|-----|-------------------------|------------|-----------|------------|-----------|---------------|
| - | | ۰ | | | | | | Nov | Jan | Mar | May | Jul | Sep |
| | 1 | | ■ Permit Acquistion Process | | Fri 7/22/16 | Wed 10/11/ | 1 | 1 | nit | Acquis | tion Proc | ess | |
| | 2 | | ▶ Flood Management Certification (FMC) | 13.75 mons | Fri 7/22/16 | Fri 8/11/17 | | 1 | nagement | Certific | ation (FN | AC). | |
| | 31 | | ■ 401 Water Quality Certification (WQC) (CTDEEP-IWRD) | 13.75 mons | Fri 7/22/16 | Fri 8/11/17 | | ty Certifi | cation (WC | (C) (CT | EEP-IWR | D) 🚩 | |
| Γ | 32 | | | 10.75 mons | Fri 7/22/16 | Fri 5/19/17 | | um | JSACE Gen | eral Per | rmit (CT (| SP) 🕶 | |
| ŀ | 33 | | Draft Permit | 30 days | Fri 7/22/16 | Fri 9/2/16 | | 1 | | - 1 | Draft Per | mit | 0% |
| | 34 | | CTDOT OEP Review | 1 mon | Fri 9/2/16 | Fri 9/30/16 | 33 | | | | TDOT OE | P Reviev | w |
| | 35 | | CTDOT EPC Review | 1 wk | Fri 9/30/16 | Fri 10/7/16 | 34 | | | | TDO | T EPC Re | eview |
| | 36 | | Draft Revisions to Permit | 20 days | Fri 10/7/16 | Fri 11/4/16 | 35 | | | | ft Revis | ions to I | Permit 1 |
| | 37 | | CTDOT OEP Review & Processing | 1 mon | Fri 11/4/16 | Fri 12/2/16 | 36 | | | | OEP Re | view & I | Processi |
| l | 38 | | CTDEEP Review, Processing & Certification | 6 mons | Fri 12/2/16 | Fri 5/19/17 | 37 | | | BY | view, Pro | cessing | & Certifi |
| | 39 | | ▶ Individual 401 WQC | 13.75 mons | Fri 7/22/16 | Fri 8/11/17 | | | | divid | ıal 401 W | QC. | |
| 1 | 48 | | ■ Inland Wetlands/Watercourses Permits (CTDEEP-IWRI) | 15.9 mons | Fri 7/22/16 | Wed 10/11/ | 1 | Waterco | urses Pern | nits (CTI | DEEP-IWE | RD) | |
| | 49 | | General Water Resource Construction Activities | 15.9 mons | Fri 7/22/16 | Wed 10/11/ | 1 | ıter Re | source Cor | structio | n Activit | ies | |
| ŀ | 50 | | Draft Permit | 30 days | Fri 7/22/16 | Fri 9/2/16 | | | | - | Draft Pen | mit | 0% |
| | 51 | | CTDOT OEP Review | 1 mon | Fri 9/2/16 | Fri 9/30/16 | 50 | 1 | | | TDOT OE | P Reviev | w=== |
| 1 | 52 | | CTDOT EPC Review | 1 wk | Fri 9/30/16 | Fri 10/7/16 | 51 | | | | TDO | T EPC Re | eview |
| 6 | 53 | | Draft Revisions to Permit | 20 days | Fri 10/7/16 | Fri 11/4/16 | 52 | | | | ft Revis | ions to I | Permit * |
| 8 | 54 | | CTDOT OEP Review & Processing | 1 mon | Fri 11/4/16 | Fri 12/2/16 | 53 | | | | OEP Re | view & I | Processi |
| 1 | 55 | | CTDOT OEP Permit Registration to CTDEEP | 3 days | Fri 10/6/17 | Wed 10/11/1 | 5,: | | | | | | |
| , | 56 | | Individual Inland Wetland & Watercourses | 13.75 mons | Fri 7/22/16 | Fri 8/11/17 | | Hini | and Wetla | nd & W | atercour | ses | |
| - | 65 | | ▶ Stormwater Permit (CTDEEP-WPED) | 7.5 mons | Fri 7/22/16 | Fri 2/17/17 | | | ater Perr | nit (CTD | EEP-WPI | D) 🔽 | |
| , | 76 | | ▶ Coastal Permits | 14.05 mons | Fri 7/22/16 | Mon 8/21/1 | | | | Coa | stal Pern | nits | |
| 1 | 108 | | Dam Permits (CTDEEP-IWRD) | 13.75 mons | Fri 7/22/16 | Fri 8/11/17 | | | Pern | nits (CTI | DEEP-IWI | RD) | |
| - | 124 | | ▶ Section 404/Section 10 Permits (USACE) | 15.75 mons | Fri 7/22/16 | Fri 10/6/17 | | D | 4/Section: | LO Perm | its (USA | (E) | |
| | 147 | | ▶ United States Coast Guard (USCG) | 45.75 | Fri 7/22/16 | Fri 10/6/17 | | 1 | States | Coast G | uard (USG | (C) | |



Project Initiation to 30%



Designer Submits Permit Needs Determination Form

Present Project At Inter-Agency Meeting

Project Initiation








30% Design

Begin Fisheries Coordination OEP Determines Permits Needed for Project


| Office/Unit | Responsibility |
|------------------|--|
| Lead Design Unit | Develop project scope |
| OEP | Environmental Review FormPermit Needs Determination Form (PNDF) |
| OEC | Task 100 – Hazardous Materials Screening |
| EPC | Facilitation of PNDF |
| H&D | Development of Hydraulic Model |

30% to 60%




| Office/Unit | Responsibility |
|------------------|---|
| Lead Design Unit | Develop design alternativesDevelop Permit Plan Set/Permits |
| OEP | Review/Provide comments on design alternativesDetermine necessary permits |
| EPC | Facilitation of determination of necessary permits Facilitate communication between engineers and planning |
| H&D | Finalize Drainage Report |
| Construction | Review/Provide constructability comments |

60% to 90%



90% to Advertise

Application



Permit
Approvals/Waiver
to Advertise


Close coordination with DEEP/ACOE Staff on timeframe of approvals.
Contracts are not awarded without a permit

Permitting Agency Coordination

- DEEP/DOT Quarterly Meetings
- Group of Eight semi-weekly meetings
 - Internal Monthly
 - With DEEP Monthly
- Interagency Review Meetings Monthly
 - Designers
 - DEEP
 - ACOE
 - EPA
- Monthly Internal Permit Priority Meetings



How are permits/commitments administered in the field?



CONSTRUCTION PHASE

- Contract Amin
- District Environmental Coordinators

OEP

- Compliance with Permits
- Env. Special Provisions
- Plantings and Invasive Species coordination

PERMIT COMMITMENT ADMINISTRATION

Environmental Compliance

- Field oversight Remediation/soil reuse
- Disposal tracking

Lead Design Unit

- Submittal Review
- RFI

Construction



- Permits transmitted to Contractor
- Pre-Construction Meeting
 - Establish Commitments
 - Separate Environmental Coordination Meeting
- Field Oversight
 - Construction Engineer
 - District Environmental Coordinator
 - OEP Water/Noise Compliance
 - Environmental Compliance Task-Based Consultant Inspector
- Progress Meetings

Environmental Summit Agenda



| Fisheries Enhancements – Fish Ladder Success | Amanda Saul OEP Water/Natural Resources |
|---|---|
| Wildlife Enhancements - Commodore Hull Bridge Falcons | Chris Samorajczyk , OEP Water /Natural Resources Brian Hess, DEEP Wildlife Diversity |
| Impact Avoidance Techniques – Charter Oak Greenway | Mike Lashua State Highway Design |
| Greenways / Community Involvement - Cheshire Heritage Trail | Vitalij Staroverov State Highway Design |
| One project - multiple considerations- CT FASTRAK | Amie Maines, Environmental Compliance Kevin Carifa, OEP Water/Noise Unit |
| Q- Bridge - DOT District & DEEP Environmental Collaboration | Heather Falzano, DOT District Environmental Coordinator Beverly Flowers, DEEP Land & Water Resources |